MISH 39

SUBCONTRACTOR MANAGEMENT PLAN

AGC CSEA Alignment

Subcontractor Management

OSHA Core Element

Communication and Coordination

Section Summary

Defines the subcontractor safety management plan including pre-qualification, site-specific requirements, and performance monitoring.

Core Values: Integrity | Honesty | Professionalism | Thoroughness

"Building projects for the client, NOT the dollar."

SUBCONTRACTOR MANAGEMENT PLAN

Document: MISH 39	**Revision:** 2	**Effective:** 04/07/2026	**Approved:** Jeremy Thamert

AGC CSEA Alignment	OSHA Core Element
Subcontractor Management	Communication and Coordination

1.0 PURPOSE

To ensure that MH Construction, Inc continues to improve the subcontractors health, safety and environmental performance and to establish a standards for pre-qualification, evaluation/selection and development of our subcontractors. This implies to all subcontractors and all MH Construction Inc. locations.

2.0 SCOPE

This implies to all subcontractors and all MH Construction Inc. Locations.

3.0 GENERAL REQUIREMENTS

3.1 All MH Construction Inc. subcontractors are to be managed in accordance with this program.

3.2 The use of subcontractors must be pre-approved by MH Construction. Approval requires as follows:

3.2.1 A formal safety review will be performed by MH Construction, which will include a review of the subcontractors safety program, safety training documentation and safety statistics.

3.2.2 The scope of the review will include the hazards and risk exposures.

3.2.3 All subcontractors must agree to abide by MH Constructions Drug and Alcohol Policy and Onsite Safety Rules throughout the duration of the work being preformed.

3.2.4 All subcontractors will be informed on the safety policies, requirements, and expectations MH Construction requires.

3.2.5 Any subcontractor that has a “NON-Approved” safety status will not be allowed on any MH Construction site until further notice.

4.0 PROCEDURE

4.1 Pre-Qualifications for subcontractors as follow:

4.1.1 Subcontractors will qualify when safety programs, safety training documents and safety statistics are reviews and meet the required standards.

4.2 Evaluation Safety Metrics will also be used for pre-qualification and selecting subcontractors. The safety metrics and scoring will need to meet the following to be considered:

4.2.1 MH Construction Subcontractor Safety Pre-Qualification Form response and subcontractor safety program documents review with a 60%(rated from 0-60points)

5.0 EVALUATION RATING AND ACCEPTANCE

5.1 The subcontractors rating system has five designations, as follows:

5.1.1 A – No restrictions. (Equals to or greater than 90 Points)

5.1.2 B – Mitigation plan must be documented & approved by MH Construction safety. (Between 80 and 89 Points) 5.1.3 C- Mitigation plan must be documented and approved by MH Construction safety and management approval in written agreement. (Between 71 and 79 points) 5.1.4 D- Mandatory commitment meeting with senior subcontractor management present, mitigation plan documented, and approved by MH Construction safety personnel; management approval in written agreement; Trained subcontractor safety personnel on site while any work is being performed under any circumstance of the number of employees on site. (Between 61 and 70 points)

5.1.5 F- Will not be considered. (Less than 60 points)

5.2 All subcontractors will be evaluated and scored by MH Construction Personnel. MH Construction Personnel will then provide Management with the scores and rankings of all subcontractors for acceptance.

5.3 MH Construction Inc. reserves the right to change a subcontractors state to “Non-Approved” if the subcontractor shows any insufficient progress towards any mitigations plan and or otherwise agreed upon criteria.

6.0 SUBCONTACTOR INVOLVEMENT

6.1 Subcontractors are required to follow and implement the work practices and systems described below, while performing work at MH Construction worksites:

6.1.1 Attend mandatory safety orientation, pre-job meeting or kick-off meeting provided by MH Construction prior to any work being performed.

6.1.2 Monitor employees for substance abuse or report non-conformities to MH Construction.

6.1.3 Ensure personnel has the required training and competency for their work.

6.1.4 Participate in MH Construction Tool Box Safety Meetings, job safety analysis, and or hazard assessments on job safety inspections.

6.1.5 Preform a pre-job safety inspections which includes an equipment inspection as well.

6.1.6 Participate in the BBS hazard reporting system.

6.1.7 Report all injuries, spills, property damages, incidents, and near misses.

6.1.8 Comply with onsite and owner client safety rules.

6.1.9 Implement MH Construction safety practices and processes as applicable.

6.1.10 Clean up and restore worksite the work performed is finished.

6.1.11 Ensure compliance with regulations at all times.

6.1.12 Post job safety performance reviews shall be conducted for subcontractors.

6.0 RECORDS

Not Applicable

7.0 REFERENCES

Not Applicable

8.0 ATTACHMENTS

Not Applicable

End of Document