MISH 08
Event Reporting of Incidents, Accidents, and Near Misses

DIGITAL ACCESS
mhc-gc.com/resources/safety-manual/section/08

DOCUMENT	MISH 08	**REVISION**	2	**EFFECTIVE**	04/07/2026
PROGRAM	MH Construction Industrial Safety & Health Program (MISH)				
LICENSES	WA: MHCONCI907R7 · OR: 765043-99 · ID: RCE-49250				

Accident Reporting Procedures

DOCUMENT	REVISION	EFFECTIVE DATE	APPROVED BY
	2	04/07/2026	Jeremy Thamert

MH CONSTRUCTION INDUSTRIAL SAFETY AND HEALTH PROGRAM

Title

EVENT REPORTING: INCIDENTS, ACCIDENTS, AND NEAR MISS'

Number

Revision 1 Approved By Jeremy Thamert 03/01/2025 Name Date Effective Date 3/1/2025 Page 1 of 8

1.0 PURPOSE

To define and implement the system for ensuring prompt and correct investigation, notification, and reporting of safety-related events that is in accordance with MH Construction Company requirements.

2.0 RESPONSIBILITY

2.1 MH Construction Key Supervisor shall be responsible for forwarding completed MH Construction Accident Report and all other safety-related documents to MH Construction Safety.

2.2 Personnel must be trained in their roles and responsibilities for incident response and incident investigation techniques.

2.3 Equipment will be provided as needed to investigate an accident which may include some or all of the following items; writing equipment such as pens/paper, measurement equipment such as tape measures and rulers, cameras, small tools, audio recorder, PPE, marking devices such as flags, equipment manuals

2.4 The Key Supervisor shall be responsible for the following event-related activities.

2.4.1 Ensuring that all events are reported immediately to the MH Construction Division Manager and Cooperate Safety.

2.4.2 Required incidents must be reported to applicable regulatory agency(s) within 8 hours of their discovery. Incidents must also be reported to the client as soon as possible, or in a timely manner (within 24 hours of incident).

2.4.3 Ensuring that the event scene is secure from disturbance and unauthorized entry until released by MH Construction Safety.

2.4.4 Assisting MH Construction with the collection of all transient evidence for the investigation and assisting with identification of witnesses.

2.4.5 Conducting investigations in accordance with this procedure.

2.4.6 Preparing reports in accordance with this procedure.

2.5 Employees shall be responsible for the following:

2.5.1 Preventing a second event, fire, injury, or further damage to the extent possible.

2.5.2 Activating emergency assistance systems when required.

2.5.3 Immediately reporting all events/accidents to supervision.

2.5.4 Securing the scene from disturbance and unauthorized entry.

2.5.5 Participating in investigations, as required.

3.0 DEFINITIONS

Event: An unplanned incident (including near miss') affecting employee health and safety or causing property/environment damage.

4.0 GENERAL REQUIREMENTS

4.1 All events, regardless of severity, shall be reported to MH Construction Key Supervisor.

4.2 All events, regardless of severity, shall be investigated and documented.

4.3 MH Construction shall ensure that injury/illness recordkeeping and reporting is performed in accordance with OSHA standards and document this determination.

4.4 MH Construction Safety shall conduct independent investigations on events at the discretion of the Division Manager.

4.5 MH Construction Safety shall review all documents and reports to ensure completeness and meaningful responses.

5.0 PROCEDURE

5.1 Reporting of Accidents/Injuries

Contractor employees receiving personal injury are encouraged to report to the nearest medical care/emergency assistance. All injuries must be reported, to MH Construction Division Manager and Safety Department.

5.1.1 Accident Reporting

5.1.1.1.1 An MH Construction Accident Report shall be completed for any of the following events:

• First Aid Injury

• Personal injury accidents as follows:

◦ OSHA Recordable Cases ◦ Receive medical attention off site

• Environmental incidents – releases and spills.

• Accidents resulting in property damage.

• Vehicle accidents resulting in damages exceeding $500.

• Near-miss incidents.

5.1.1.2 The Accident Report shall be completed in detail by the Key Supervisor describing the following items:

• Activity in progress at time of accident/incident.

• Events, beginning with initiation of the activity and ending with nature and extent of the injury/damage.

• Accident causes (direct cause, contributory cause, and root cause) including conditions and/or actions and mitigating factors influencing them.

• Corrective action planned and taken to prevent the accident/incident from reoccurring.

5.1.1.3 Within 24 hours of the event, the Accident Report is submitted to MH Construction Safety.

5.1.2 Accident Reports or an in depth report may be required to be documented on the Accident Report form (see 8-A).

5.2 Follow-up Actions for Events/Accidents: The following actions shall be implemented:

5.2.1 Prevent immediate second event, fire, or emergency n the facility and/or area.

5.2.2 Implement rescue procedures and/or appropriate medical care for injured personnel.

5.2.3 Notify MH Construction Division Manager and Safety Department.

5.2.4 Secure the event scene from disturbance and unauthorized entry pending arrival of MH Construction Safety.

5.2.5 Keep equipment or articles involved in the event from being operated, moved, or otherwise altered or repaired.

5.2.6 If determined necessary, obtain photographs of the event scene and any equipment involved, e.g., motor vehicles, excavating equipment, ladders, scaffolds, etc.

5.2.7 Assist MH Construction and/or identify witnesses; secure statements from those who were directly involved or who may have witnessed the event.

5.2.8 With MH Construction, develop plans for the reactivation of the facility, area process, or operations.

5.2.9 If an MH Construction investigation is conducted, assign an individual to serve as liaison to arrange for needed assistance and gathering evidence.

5.2.10 Complete required reports.

5.2.11 Participate in Root Cause Determinations, facilitated by MH Construction Management.

5.3 Tracking and Trending

5.3.1 A lessons-learned shall be generated from all injuries/accidents that are determined recordable or property damage resulting in $1000 of damage. The lessons-learned with be forwarded to all Key Supervisors for discussion in the following safety meetings.

5.3.2 The accident report will be inputted into the Safety departments trending and tracking system to help identify trends.

5.3.3 The trends report will be covered quarterly with Division Managers.

6.0 RECORDS

The following records are submitted to MH Construction and maintained by the in accordance with this procedure:

- Accident Report
- OSHA 300 logs (submit only when requested)
- Lessons Learned

7.0 REFERENCES

29 CFR 1904 Occupational Safety and Health Act

8.0 ATTACHMENTS

MISH 8-A MH Construction Accident Report MISH 8-B Lessons Learned

MH CONSTRUCTION ACCIDENT REPORT

OSHA/case no Employee Name:

SSN: Job Title: Date of Accident: Location Event (job site/ bldg/facility) Time of Accident:

Division Manager Supervisor Name (foremen/supt.) Division and Department

MH Construction Inc HVAC Heavy Commercial Piping Heavy Commercial Industrial (food processing) Light Commercial (HVAC) Special Projects/Industrial Refrigeration Design/Build Commercial Event (begin with initiating action and end with nature, extent of injury/damage(such as laceration left index finger), and treatment provided):

Prevention – Actions taken (describe measures taken to prevent a similar event): Date Completed by:

Activity in progress at time of accident (what was the employee work assignment the day of the injury?)

Was employee wearing PPE? Yes No What type? If vehicle was employee wearing seat belt? Yes No Did injury/illness require additional medical treatment beyond first aid? Yes No If yes, medical provider name and phone number:

ROOT CAUSE CODES – CHECK ONLY ONE

(The one root cause that would have prevented the incident)

EQUIPMENT/MATERIAL PROBLEM

1A Defective or Failed Part 1B Defective or Failed Material 1C Defective weld, braze, or soldered joint 1D Manufacture shipping or marking error 1E Electrical or instrument noise 1F Contaminant 1G End of life failure (equipment or material)

PROCEDURE PROBLEM

2A Defective or inadequate procedure 2B Lack of procedure

PERSONNEL ERROR

3A Inattention to detail 3B Procedure not used or used incorrectly 3C Communication problem 3D Other human error

DESIGN PROBLEM

4A Inadequate work environment 4B Inadequate or defective design 4C Error in equipment or material selection 4D Drawing, specification, or data error

TRAINING DEFICIENCY

5A No training provided 5B Insufficient practice or hands on experience 5C Inadequate content 5D Insufficient refresher training 5E Inadequate presentation or materials

MANAGEMENT PROBLEM

6A Inadequate administrative control 6B Work organization/planning deficiency 6C Inadequate supervision MANAGEMENT PROBLEM (cont)

6D Improper resource allocation 6E Policy not adequately defined, disseminated, or enforced 6F Other management problem

EXTERNAL PHENOMENON

7A Weather or ambient condition 7B Power failure or transient 7C External fire or explosion 7D Theft, tampering, sabotage, or vandalism Did employee die? Yes No Was the employee hospitalized overnight? Yes No

MH CONSTRUCTION ACCIDENT REPORT CONTINUED

OSHA/case number

CHECK ALL THAT APPLY

Injury/illness Potential exposure Near miss Other Spill Fire Equipment/vehicle operator Property Damage Est Cost $_____ Vehicle accident Est Cost $_____

CAUSES

The condition/act hat actually caused the incident UNSAFE CONDITION (check only one)

UNSAFE ACT

A No unsafe condition B Defective source of injury (dull, rough, sharp, slippery, broken, etc) C Improper or inadequate clothing D Unsafe method or procedure E Unsafe placement or storage F Inadequate guarding G Inadequate illumination H Inadequate ventilation I Unsafe walk/work surface J Other _____

_____

K No unsafe act L Working on moving, energized, pressurized equipment M Failure to wear protective equipment N Operating without authority O Failure to secure or warn P Horseplay Q Improper use of equipment R Taking an unsafe position or posture S Inattention to footing or surrounding T Making safety devices inoperative U Undue haste V Equipment/vehicle operator driving error W Unsafe loading, placing, mixing, etc X Using unsafe equipment Y. Other Describe:

_____

_____

EMPLOYEE

Home Address:

Age: Sex:

Home phone number: Experience: Time since hire: Explain what happened in detail

Recommendations to prevent recurrence of accident:

Employee Signature: Date:

Supervisor Signature:

Date:

LESSON LEARNED

What happened:

What was the outcome:

What corrective measures where taken:

MISH 08 — Event Reporting of Incidents, Accidents, and Near Misses

Scan to view this section online, download the PDF, or access the full MH Construction Safety Manual.

https://www.mhc-gc.com/resources/safety-manual/section/event-reporting-of-incidents-accidents-and-near-misses