



CONTROLLED ENTERPRISE DOCUMENT

TBT-01.06 | Scaffolding Safety And Inspections

MH Construction, INC Enterprise Management System

Document family: TOOLBOX TALK LIBRARY

Document title: TBT-01.06 | Scaffolding Safety And Inspections

Version: 1.0 | Lifecycle: Rough Draft

Use only after required functional, technical, field-usability, and approval gates are complete.

Control: Version 1.0 | Status Rough Draft | Author and Chief Editor: Matt Ramsey | Co-Editor: Todd Shoeff | Final Approver: Jeremy Thamert

TBT-01.06: Scaffolding Safety & Inspections

CSI Division: Div 01 | OSHA Reference: 29 CFR 1926.454

Delivery: Mandatory before erecting, dismantling, or working on scaffolding.

DIRECTIVE — Policy Standard

All scaffolding must be erected, moved, dismantled, or altered only under the supervision of a Competent Person.

GENERAL ORDER — Procedure

Scaffolds must be inspected by the Competent Person before each work shift. The scaffold must be fully planked, plumb, and equipped with guardrails, midrails, and toeboards if over 10 feet high.

Key Hazards & Mitigation (The 'What If'):

- Missing Tags: If a scaffold does not have a green 'Safe for Use' tag signed by the Competent Person for today's date, do not climb it. Treat it as unsafe.
- Overloading: If masonry crews stack blocks on a light-duty scaffold, the scaffold could collapse. Ensure the load does not exceed the scaffold's rated capacity (e.g., 25 psf for light duty).
- Base Support: If a scaffold leg is resting on a brick or scrap wood, stop work. Scaffold legs must rest on base plates and adequate mudsills.

FIELD INSTRUCTION — Execution

FIELD INSTRUCTION: Foremen must verify the daily Competent Person inspection tag on all active scaffolds today. Log attendance on MISH-F-10.1 and complete MISH-F-22.1.

Attendance Roster (Log on MISH-F-10.1):

Print Name	Signature	Company/Trade