



CONTROLLED ENTERPRISE DOCUMENT

TBT-01.09 | Change Order Scope And Safety Review

MH Construction, INC Enterprise Management System

Document family: TOOLBOX TALK LIBRARY

Document title: TBT-01.09 | Change Order Scope And Safety Review

Version: 1.0 | Lifecycle: Rough Draft

Use only after required functional, technical, field-usability, and approval gates are complete.

Control: Version 1.0 | Status Rough Draft | Author and Chief Editor: Matt Ramsey | Co-Editor: Todd Shoeff | Final Approver: Jeremy Thamert

TBT-01.09: Change Order Scope & Safety Review

CSI Division: Div 01 | OSHA Reference: MH Standard

Delivery: Mandatory for all Superintendents and Foremen executing Change Order work.

DIRECTIVE — Policy Standard

A Change Order alters the baseline scope, which alters the baseline hazard profile. No Change Order work may begin until a new Job Hazard Analysis (JHA) is written specifically for the new scope.

GENERAL ORDER — Procedure

The Foreman must not accept verbal 'go-aheads' from the client that alter the safety plan. The Change Order must be logged on FIN-F-04.1, and the safety implications must be briefed to the crew.

Key Hazards & Mitigation (The 'What If'):

- **Unexpected Utilities:** If a Change Order requires trenching in a new area of the site, the old utility locate is void. A new locate must be called in and cleared before digging.
- **Schedule Pressure:** If a Change Order compresses the schedule, the risk of rushing and cutting corners increases. The Foreman must enforce the standard work pace. Safety does not accelerate.
- **New Materials:** If a Change Order introduces a new architectural finish, it likely introduces a new chemical. Ensure the new SDS is obtained before the material arrives.

FIELD INSTRUCTION — Execution

FIELD INSTRUCTION: Foremen must review any active Change Orders today and ensure the daily JHA (MISH-F-09.2) explicitly covers the new hazards. Log attendance on MISH-F-10.1.

Attendance Roster (Log on MISH-F-10.1):

Print Name	Signature	Company/Trade