



CONTROLLED ENTERPRISE DOCUMENT

# TBT-01.10 | Closeout Punch List Safety Focus

MH Construction, INC Enterprise Management System

Document family: TOOLBOX TALK LIBRARY

Document title: TBT-01.10 | Closeout Punch List Safety Focus

Version: 1.0 | Lifecycle: Rough Draft

Use only after required functional, technical, field-usability, and approval gates are complete.

---

Control: Version 1.0 | Status Rough Draft | Author and Chief Editor: Matt Ramsey | Co-Editor: Todd Shoeff | Final Approver: Jeremy Thamert

TBT-01.10: Closeout Punch List Safety Focus

CSI Division: Div 01 | OSHA Reference: MH Standard  
Delivery: Mandatory for all crews executing final punch list and touch-up work.

DIRECTIVE — Policy Standard

The final 5% of a project is statistically the most dangerous due to complacency, reduced supervision, and the mix of construction crews with client personnel moving in.

GENERAL ORDER — Procedure

All MH safety standards (PPE, fall protection, LOTO) remain in full effect until the final punch list item is signed off. 'It's just a quick touch-up' is not an excuse to leave the hard hat in the truck.

Key Hazards & Mitigation (The 'What If'):

- Working Around the Client: If client staff are moving furniture into the building while MH is painting the lobby, the work area must be barricaded to protect the public from ladders and wet paint.
- Live Systems: During closeout, all electrical and mechanical systems are live. LOTO is critical for any final adjustments. Do not assume a breaker is off just because it was off yesterday.
- Housekeeping: As subs demobilize, trash and scrap often accumulate. The site must be broom-swept daily to prevent fire hazards and slip/trip/falls.

FIELD INSTRUCTION — Execution

FIELD INSTRUCTION: Foremen must review PEP-F-08.1 (Closeout Punch List) and assign specific safety controls for each remaining task. Log attendance on MISH-F-10.1.

Attendance Roster (Log on MISH-F-10.1):

| Print Name | Signature | Company/Trade |
|------------|-----------|---------------|
|            |           |               |
|            |           |               |
|            |           |               |
|            |           |               |
|            |           |               |