



CONTROLLED ENTERPRISE DOCUMENT

TBT-03.04 | Concrete Formwork And Rebar Impalement

MH Construction, INC Enterprise Management System

Document family: TOOLBOX TALK LIBRARY

Document title: TBT-03.04 | Concrete Formwork And Rebar Impalement

Version: 1.0 | Lifecycle: Rough Draft

Use only after required functional, technical, field-usability, and approval gates are complete.

Control: Version 1.0 | Status Rough Draft | Author and Chief Editor: Matt Ramsey | Co-Editor: Todd Shoeff | Final Approver: Jeremy Thamert

TBT-03.04: Concrete Formwork & Rebar Impalement

CSI Division: Div 03 | Track Assignment: Track 1 Civil & Earthwork

DIRECTIVE

All protruding reinforcing steel (rebar) onto which workers could fall must be guarded to eliminate the hazard of impalement.

GENERAL ORDER

Use approved rebar caps (mushroom caps with steel reinforcement) or bend the rebar. Standard plastic caps without steel plates are not acceptable for fall protection.

Key Hazards & Mitigation (The 'What If')

- Worker working above unguarded rebar — stop work, install steel-reinforced caps or cover with lumber.
- Formwork shifts during pour — evacuate the immediate area, do not attempt to brace it while under pressure.
- Tripping over tied rebar mat — maintain clear, designated walkways across the mat.

FIELD INSTRUCTION

Foreman: Inspect all vertical rebar for approved impalement protection before any elevated work begins above it.

Attendance Roster (MISH-F-10.1)

Print Name	Signature	Date

Toolbox Talk Documentation & Sign-Off

This Toolbox Talk (TBT) is a mandatory component of the MH Construction, INC Industrial Safety & Health (MISH) Program. All site personnel, including subcontractors and temporary laborers, must attend this briefing before commencing related work activities.

The Site Safety Commander or designated Foreman is responsible for delivering this content, ensuring comprehension, and documenting attendance. Failure to adhere to the safety protocols outlined herein may result in disciplinary action up to and including removal from the jobsite.

By signing the daily attendance log (Form MISH-F-10.1), you acknowledge that you have received, understood, and agree to comply with the safety directives presented in this Toolbox Talk.