



CONTROLLED ENTERPRISE DOCUMENT

TBT-04.01 | Masonry Wall Bracing And Scaffolding

MH Construction, INC Enterprise Management System

Document family: TOOLBOX TALK LIBRARY

Document title: TBT-04.01 | Masonry Wall Bracing And Scaffolding

Version: 1.0 | Lifecycle: Rough Draft

Use only after required functional, technical, field-usability, and approval gates are complete.

Control: Version 1.0 | Status Rough Draft | Author and Chief Editor: Matt Ramsey | Co-Editor: Todd Shoeff | Final Approver: Jeremy Thamert

TBT-04.01: Masonry Wall Bracing & Scaffolding

CSI Division: Div 04 | Track Assignment: Track 2 Structural & Steel

DIRECTIVE

All unbraced masonry walls over 8 feet in height must be adequately braced to prevent overturning and collapse.

GENERAL ORDER

Bracing must remain in place until the roof structure or final lateral supports are tied in. Masonry scaffolding must be built to handle the heavy load of block and mortar.

Key Hazards & Mitigation (The 'What If')

- Wind picks up during block laying — stop work and install temporary bracing.
- Scaffold overloaded with block — stop loading, distribute weight, re-inspect.
- Silica dust from block cutting — wet cut only, wear N95.

FIELD INSTRUCTION

Foreman: Inspect the wall bracing plan and verify wind limits before the shift begins.

Attendance Roster (MISH-F-10.1)

Print Name	Signature	Date

Toolbox Talk Documentation & Sign-Off

This Toolbox Talk (TBT) is a mandatory component of the MH Construction, INC Industrial Safety & Health (MISH) Program. All site personnel, including subcontractors and temporary laborers, must attend this briefing before commencing related work activities.

The Site Safety Commander or designated Foreman is responsible for delivering this content, ensuring comprehension, and documenting attendance. Failure to adhere to the safety protocols outlined herein may result in disciplinary action up to and including removal from the jobsite.

By signing the daily attendance log (Form MISH-F-10.1), you acknowledge that you have received, understood, and agree to comply with the safety directives presented in this Toolbox Talk.