



CONTROLLED ENTERPRISE DOCUMENT

TBT-05.01 | Steel Erection And Decking Safety

MH Construction, INC Enterprise Management System

Document family: TOOLBOX TALK LIBRARY

Document title: TBT-05.01 | Steel Erection And Decking Safety

Version: 1.0 | Lifecycle: Rough Draft

Use only after required functional, technical, field-usability, and approval gates are complete.

Control: Version 1.0 | Status Rough Draft | Author and Chief Editor: Matt Ramsey | Co-Editor: Todd Shoeff | Final Approver: Jeremy Thamert

TBT-05.01: Steel Erection & Decking Safety

CSI Division: Div 05 | OSHA Reference: 29 CFR 1926.750
Delivery: Mandatory for all ironworkers and structural steel crews.

DIRECTIVE — Policy Standard

Steel erection must proceed systematically with a minimum of four bolts per connection (or equivalent) before releasing the hoisting line. Fall protection is required for all connectors above 15 feet.

GENERAL ORDER — Procedure

Controlled Decking Zones (CDZ) must be clearly marked and restricted to authorized decking personnel only. Materials staged on the deck must be secured immediately against wind displacement.

Key Hazards & Mitigation (The 'What If'):

- Double Connections: If a worker must share a bolt hole for two beams on a column web, the first beam must be secured with a seated connection or staggered bolts before the second beam is swung in.
- Unsecured Decking: If a bundle of metal decking is landed on the structure but not immediately spread and fastened, it must be banded or wire-tied to the structural frame to prevent wind uplift.
- Walking the Top Flange: If an ironworker must traverse a beam without a continuous tie-off cable, they must straddle or bottom-flange walk. 'Cooning' the beam is the standard.

FIELD INSTRUCTION — Execution

FIELD INSTRUCTION: Foremen must verify that all perimeter safety cables are installed and tensioned immediately after the steel is bolted up in each zone. Log attendance on MISH-F-10.1.

Attendance Roster (Log on MISH-F-10.1):

Print Name	Signature	Company/Trade