



CONTROLLED ENTERPRISE DOCUMENT

TBT-06.02 | Wood Truss Installation And Bracing

MH Construction, INC Enterprise Management System

Document family: TOOLBOX TALK LIBRARY

Document title: TBT-06.02 | Wood Truss Installation And Bracing

Version: 1.0 | Lifecycle: Rough Draft

Use only after required functional, technical, field-usability, and approval gates are complete.

Control: Version 1.0 | Status Rough Draft | Author and Chief Editor: Matt Ramsey | Co-Editor: Todd Shoeff | Final Approver: Jeremy Thamert

TBT-06.02: Wood Truss Installation & Bracing

CSI Division: Div 06 | Track Assignment: Track 2 Structural & Steel

DIRECTIVE

Wood trusses are unstable until fully braced. Temporary bracing must be installed strictly according to the manufacturer's engineering plan.

GENERAL ORDER

Do not overload unbraced trusses with building materials. Workers must tie off when walking the top plate or truss chords.

Key Hazards & Mitigation (The 'What If')

- Truss begins to bow or roll during installation — stop, apply temporary lateral bracing immediately.
- Stack of plywood placed on unbraced trusses — remove the load, distribute weight only after permanent bracing is installed.
- Worker walking the top plate without fall protection — enforce 100% tie-off or use aerial lifts.

FIELD INSTRUCTION

Foreman: Review the manufacturer's temporary bracing plan with the crew before the first truss is lifted.

Attendance Roster (MISH-F-10.1)

Print Name	Signature	Date

Toolbox Talk Documentation & Sign-Off
This Toolbox Talk (TBT) is a mandatory component of the MH Construction, INC Industrial Safety & Health (MISH) Program. All site personnel, including subcontractors and temporary laborers, must attend this briefing before commencing related work activities.

The Site Safety Commander or designated Foreman is responsible for delivering this content, ensuring comprehension, and documenting attendance. Failure to adhere to the safety protocols outlined herein may result in disciplinary action up to and including removal from the jobsite.

By signing the daily attendance log (Form MISH-F-10.1), you acknowledge that you have received, understood, and agree to comply with the safety directives presented in this Toolbox Talk.