



CONTROLLED ENTERPRISE DOCUMENT

TBT-07.03 | Waterproofing Solvents And Confined Vapors

MH Construction, INC Enterprise Management System

Document family: TOOLBOX TALK LIBRARY

Document title: TBT-07.03 | Waterproofing Solvents And Confined Vapors

Version: 1.0 | Lifecycle: Rough Draft

Use only after required functional, technical, field-usability, and approval gates are complete.

Control: Version 1.0 | Status Rough Draft | Author and Chief Editor: Matt Ramsey | Co-Editor: Todd Shoeff | Final Approver: Jeremy Thamert

TBT-07.03: Waterproofing Solvents & Confined Vapors

CSI Division: Div 07 | Track Assignment: Track 3 MEP & Interior

DIRECTIVE

Many waterproofing membranes and primers contain volatile solvents. Adequate ventilation must be maintained to prevent vapor accumulation and flash fires.

GENERAL ORDER

Eliminate all ignition sources in the area. Do not use solvent-based products in below-grade or confined areas without mechanical ventilation.

Key Hazards & Mitigation (The 'What If')

- Strong solvent smell accumulates in a basement — evacuate the area, set up exhaust fans.
- Worker sparks a lighter near the waterproofing operation — stop work, enforce strict no-smoking/no-ignition rules.
- Dizziness or headache while applying primer — move to fresh air immediately, check SDS.

FIELD INSTRUCTION

Foreman: Verify mechanical ventilation is running and all ignition sources are eliminated before opening solvent containers.

Attendance Roster (MISH-F-10.1)

Print Name	Signature	Date

Toolbox Talk Documentation & Sign-Off

This Toolbox Talk (TBT) is a mandatory component of the MH Construction, INC Industrial Safety & Health (MISH) Program. All site personnel, including subcontractors and temporary laborers, must attend this briefing before commencing related work activities.

The Site Safety Commander or designated Foreman is responsible for delivering this content, ensuring comprehension, and documenting attendance. Failure to adhere to the safety protocols outlined herein may result in disciplinary action up to and including removal from the jobsite.

By signing the daily attendance log (Form MISH-F-10.1), you acknowledge that you have received, understood, and agree to comply with the safety directives presented in this Toolbox Talk.