



CONTROLLED ENTERPRISE DOCUMENT

TBT-11.02 | Equipment Mobilization And Site Setup

MH Construction, INC Enterprise Management System

Document family: TOOLBOX TALK LIBRARY

Document title: TBT-11.02 | Equipment Mobilization And Site Setup

Version: 1.0 | Lifecycle: Rough Draft

Use only after required functional, technical, field-usability, and approval gates are complete.

Control: Version 1.0 | Status Rough Draft | Author and Chief Editor: Matt Ramsey | Co-Editor: Todd Shoeff | Final Approver: Jeremy Thamert

TBT-11.02: Equipment Mobilization & Site Setup

CSI Division: Div 11 | OSHA Reference: 29 CFR 1926.602

Delivery: Mandatory before offloading heavy equipment or establishing site laydown yards.

DIRECTIVE — Policy Standard

All heavy equipment mobilization must follow a pre-planned route, utilizing designated spotters during all backing and offloading operations.

GENERAL ORDER — Procedure

The Foreman must walk the offload zone prior to the lowboy's arrival to identify overhead power lines, soft ground, and pedestrian traffic routes. Spotters must wear high-visibility apparel and maintain eye contact with the operator.

Key Hazards & Mitigation (The 'What If'):

- Overhead Power Lines: If the lowboy must pass under power lines, verify the 10-foot minimum clearance rule. If clearance is questionable, stop and contact the utility provider.
- Ramp Slip: If it is raining or the equipment tracks are muddy, the risk of sliding off the lowboy ramps increases. Clean the tracks and ramps, and ensure the lowboy is parked on level, stable ground.
- Spotter Blind Spot: If the operator loses sight of the spotter in their mirrors, they must stop the machine immediately. Do not move until visual contact is re-established.

FIELD INSTRUCTION — Execution

FIELD INSTRUCTION: Foremen must review PEP-F-02.1 (Project Initiation Checklist) and complete MISH-F-40.1 (Daily Equipment Inspection) immediately after offload. Log attendance on MISH-F-10.1.

Attendance Roster (Log on MISH-F-10.1):

Print Name	Signature	Company/Trade