



CONTROLLED ENTERPRISE DOCUMENT

TBT-23.01 | Hvac Rigging And Roof Installations

MH Construction, INC Enterprise Management System

Document family: TOOLBOX TALK LIBRARY

Document title: TBT-23.01 | Hvac Rigging And Roof Installations

Version: 1.0 | Lifecycle: Rough Draft

Use only after required functional, technical, field-usability, and approval gates are complete.

Control: Version 1.0 | Status Rough Draft | Author and Chief Editor: Matt Ramsey | Co-Editor: Todd Shoeff | Final Approver: Jeremy Thamert

TBT-23.01: HVAC Rigging & Roof Installations

CSI Division: Div 23 | OSHA Reference: 29 CFR 1926.251
Delivery: Mandatory for mechanical crews setting RTUs (Roof Top Units) or heavy ductwork.

DIRECTIVE — Policy Standard

All RTU crane picks must utilize spreader bars to prevent the rigging slings from crushing the unit's sheet metal casing.

GENERAL ORDER — Procedure

Workers receiving the RTU on the roof must be tied off if working within 6 feet of the edge. Tag lines must be used to guide the unit onto the curb—never place hands between the unit and the curb.

Key Hazards & Mitigation (The 'What If'):

- Wind Catching the Unit: If a large RTU is hoisted in a 15 mph wind, it acts like a sail. The tag line operators must be positioned to control the spin without being pulled off the roof.
- Crush Point at the Curb: If the unit is swinging slightly as it comes down, a worker trying to align the corner with their hands will lose their fingers. Use a pry bar to make final adjustments once the weight is on the curb.
- Unsecured Ductwork: If large spiral duct is staged on the roof before installation, it will roll off in high winds. Chock and strap all staged ductwork immediately.

FIELD INSTRUCTION — Execution

FIELD INSTRUCTION: Foremen must verify the rigging configuration and tag line assignments before the crane hooks the RTU. Log attendance on MISH-F-10.1.

Attendance Roster (Log on MISH-F-10.1):

Print Name	Signature	Company/Trade