



CONTROLLED ENTERPRISE DOCUMENT

TBT-26.03 | Temporary Lighting And Gfci Protection

MH Construction, INC Enterprise Management System

Document family: TOOLBOX TALK LIBRARY

Document title: TBT-26.03 | Temporary Lighting And Gfci Protection

Version: 1.0 | Lifecycle: Rough Draft

Use only after required functional, technical, field-usability, and approval gates are complete.

Control: Version 1.0 | Status Rough Draft | Author and Chief Editor: Matt Ramsey | Co-Editor: Todd Shoeff | Final Approver: Jeremy Thamert

TBT-26.03: Temporary Lighting & GFCI Protection

CSI Division: Div 26 | OSHA Reference: 29 CFR 1926.405
Delivery: Mandatory for all crews utilizing temporary power on site.

DIRECTIVE — Policy Standard

All 120-volt, single-phase, 15- and 20-ampere receptacle outlets on construction sites must have Ground-Fault Circuit Interrupter (GFCI) protection.

GENERAL ORDER — Procedure

Temporary lighting strings must be suspended by their non-conductive molded hangers, not by the electrical wire itself. Bulbs must be protected by wire guards.

Key Hazards & Mitigation (The 'What If'):

- Daisy-Chaining Cords: If a crew plugs three 100-foot extension cords together to reach a work area, the voltage drop will damage tools and create a fire hazard. Use a temporary spider box closer to the work.
- Missing Ground Prong: If an extension cord or tool is missing the third (ground) prong, it must be cut and thrown away. Do not plug it in.
- Water in the Box: If a temporary power box is sitting in a puddle after a rainstorm, do not touch it. Have the electrician elevate it and verify the GFCI is functioning.

FIELD INSTRUCTION — Execution

FIELD INSTRUCTION: Foremen must instruct crews to inspect all extension cords for cuts and missing ground prongs before plugging in today. Log attendance on MISH-F-10.1.

Attendance Roster (Log on MISH-F-10.1):

Print Name	Signature	Company/Trade