



CONTROLLED ENTERPRISE DOCUMENT

TBT-33.02 | Manhole Installation And Confined Space

MH Construction, INC Enterprise Management System

Document family: TOOLBOX TALK LIBRARY

Document title: TBT-33.02 | Manhole Installation And Confined Space

Version: 1.0 | Lifecycle: Rough Draft

Use only after required functional, technical, field-usability, and approval gates are complete.

Control: Version 1.0 | Status Rough Draft | Author and Chief Editor: Matt Ramsey | Co-Editor: Todd Shoeff | Final Approver: Jeremy Thamert

TBT-33.02: Manhole Installation & Confined Space

CSI Division: Div 33 | Track Assignment: Track 1 Civil & Earthwork

DIRECTIVE

Setting precast manholes requires heavy rigging. Entering a manhole to grout pipes or pull forms is a Permit-Required Confined Space entry.

GENERAL ORDER

Never enter a manhole without testing the atmosphere first, even if it is newly installed. Use a tripod and winch for all entries.

Key Hazards & Mitigation (The 'What If')

- Gas monitor alarms during entry — evacuate the manhole immediately, ventilate, retest.
- Rigging chain twists while setting a manhole section — lower the section, untwist the chain, re-lift.
- Worker tries to climb down without a harness — stop, enforce the use of the retrieval harness and tripod.

FIELD INSTRUCTION

Foreman: The Confined Space Entry Permit (MISH-F-32.1) must be signed and posted at the manhole before anyone breaks the plane of the opening.

Attendance Roster (MISH-F-10.1)

Print Name	Signature	Date